

DEPERMING JARVIS GETS ZAPPED

THE SHIP WAS DEPERMED AT PEARL HARBOR DEPERMING FACILITY. DEPERMING IS A MAGNETIC SILENCING TREATMENT OF THE VESSEL. IT WOULD HELP PROTECT JARVIS FROM MAGNETIC SENSITIVE MINES IN A WARTIME SITUATION.

THE PROCESS TOOK TWO DAYS AND WAS AN ALL HANDS EVOLUTION AS CABLES HAD TO BE WRAPPED AROUND THE SHIP. ALL COMPUTERS, MAGNETIC TAPES, CREDIT CARDS, ETC. HAD TO BE REMOVED FROM THE SHIP.

THE ACTUAL DEPERMING TREATMENT LASTED 5 HOURS. THE CABLES WERE CHARGED WITH 3500 AMPS WHICH WAS SO STRONG THAT EACH PULSE WAS ONLY 1 MINUTE LONG FOLLOWED BY 9 MINUTES OF COOLING TIME.

